

---

# BLACKBURN BRIDGE REPLACEMENT

## OVER EDWARDS CREEK

**CLIENT:** Macaw Macdonald Ltd. completed the design and construction of an RTAC weight rated, 21 meter single span bridge. The existing steel truss bridge was removed and replaced with a new bridge comprised of a steel H pile foundation, precast prestressed concrete girders and precast concrete retaining walls.

**RURAL**

**MUNICIPALITY**

**OF DAUPHIN**



**DESCRIPTION:**

**REMOVE AND**

**REPLACE AN**

**EXISTING STEEL**

**TRUSS BRIDGE**

